



# PROPOSAL

Number: P126  
Date: 9/16/2011

Ian S. Jameson  
437 West Gay St.  
West Chester, PA 19380  
Direct: 484.368.2579  
[ian@waterproofcaulking.com](mailto:ian@waterproofcaulking.com)

Prepared for:  
Tom Clark  
West Chester University  
201 Carter Drive  
West Chester, PA 19383

## Scope of Work:

Specified caulking and masonry repair on WCU library building

### This Includes:

#### ROOFTOP

Cut out failed caulk on interior perimeter and exterior perimeter of coping stones on roof as well as median joints on coping stones.  
Install backer rod  
Install Sika Polyurethane caulk and tool smooth. Colors specified by owner

#### FACADES

##### Caulking

Cut out failed caulk around windows, coping stones, and recessed architectural details  
\*\*\*This includes top 2 floors only\*\*\*  
Install a Sika Polyurethane colors specified by owner  
Tool smooth

##### Masonry

Repoint 2 masonry horizontal joints located under top two floors where necessary  
Fix only areas where there are bulges or masonry blowouts ALONG ENTIRE FAÇADE JOINT  
\*\*\*This does not include chipping out entire joint and replacing it\*\*\*

## COST:

### PLAN A

Includes rooftop caulking and fixing 2 facades

|                    |         |
|--------------------|---------|
| Labor              | \$5,560 |
| 20 ft Spider Swing | \$2,500 |
| Materials          | \$1,498 |
| Ropes and Rigging  | \$400   |

*# 9958.-*