



PHONE : 717- 938 - 0591 FAX: 717- 938 - 4091

ESTIMATE

CUSTOMER INFORMATION

DATE: 2/27/12

NAME PA State System of Higher Education, PASSHE
ADDRESS Dixon University Center ATTN: Mr. Thomas O. Morgan
 2986 North 2nd Street, Harrisburg, PA 17110-1201

MEMBER BBB started in 1992

PHONE Office: 720-4087 Email: tmorgan@passhe.edu

WORK TO BE PERFORMED - resurface area approx. 17' x 135'

- Use milling machine to mill adjoining asphalt areas
- Clean and/or regrade all area(s) to be paved
- Remove any high area(s) and prefill any low area(s)
- String line and pin all area(s) for straight edges
- Apply tack coat (glue) to existing asphalt prior to resurfacing
- Machine apply 2" of ID2 wearing course asphalt (fine topcoat)
- Compress asphalt with vibratory roller and plate tamper
- Tar seal edges / joints with AC20 hot tar

WORK TO BE PERFORMED - resurface area approx. 18' x 186'

- Remove area at entrance as discussed
- Use milling machine to mill adjoining asphalt areas
- Clean and/or regrade all area(s) to be paved
- Remove any high area(s) and prefill any low area(s)
- String line and pin all area(s) for straight edges
- Apply tack coat (glue) to existing asphalt prior to resurfacing
- Machine apply 2" of ID2 wearing course asphalt (fine topcoat)
- Compress asphalt with vibratory roller and plate tamper
- Tar seal edges / joints with AC20 hot tar

TOTAL: \$9960.00

License # PA06GHIC: 000369

SPECIFICATIONS

- JR's will inspect quality of subbase to ensure a minimum of 4" to 6" of stone base
- JR's will layout and field mark all area(s) to be paved as indicated
- JR's will compact subbase material with vibratory roller to ensure proper strength to support asphalt paving
- JR's will compress asphalt at each course with vibratory roller and plate tamper to ensure proper compaction

All work to be performed will be installed in a neat, clean and professional manner
 Amount of asphalt installed is measured at a depth PRIOR to compaction
 Please allow 48 to 72 hours for drying time - Avoid power steering marks on new asphalt

GUARANTEE

GENERAL - JR's Driveway Service will guarantee against defects in material or workmanship which result in settlement of any specific area for 2 years from completion of work
 NEW CONSTRUCTION - JR's is not responsible for any settlement or cracking of paving due to improper placement of subbase or back fill installed by others
 OTHER - JR's cannot guarantee against weeds, power steering marks, damage caused by improper water drainage and drainage problems resulting from existing ground slopes and grading conditions

CONTRACTOR:

THANK YOU

Upon completion, please remit to: JR's Driveway Service, P.O. Box 272, Lewisberry PA, 17339 - THANK YOU
 TERMS: Payment due upon completion of work - Unpaid invoices are subject to a 10% late fee per month